


SLAC Update



Presentation by
Jonathan Dorfan, Director
at
HEPAP
November 7, 2002



PEP-II and BABAR


- ✍ **Run 2 concluded June 2002 with total integrated luminosity of 100 fb^{-1}**
- ✍ **4 1/2 month down time activities will be completed on-time Nov. 15, 2002 at which time we commence Run 3**
 - ✍ **PEP-II luminosity reach improved to $10^{34} \text{ cm}^{-2} \text{ sec}^{-1}$**
 - ✍ **Several improvements to BABAR**



PEP-II / BABAR Performance

Daily recorded lumi

002/07/08 17.14




Records for recorded lumi

shift: 105 pb^{-1}
24 hrs: 303
Week: 1790
Month: 6666

- Within 4 months of first BaBar collisions, setting world records for luminosity delivered
- Within first year, design goals for luminosity delivered to detector met and exceeded



2002/07/08 17.14






Interaction point improvements for reduced beam heating

- ✍ IP bellows cooling (air and water)
- ✍ New Q2 chamber
- ✍ New Q2 bellows
- ✍ New beam loss monitors
- ✍ Repaired vacuum valves
- ✍ > x5 improvement in beam heating capacity



Forward Vertex Chamber Bellows Cooling Installation





Higher Beam Currents

- ✍ Installed two new HER RF stations
- ✍ Commission one new LER RF station
- ✍ Shortened abort gap from 5% to 2.5%
- ✍ Improved cooling on bunch feedback kickers
- ✍ More shielding near LER IR collimators for backgrounds
- ✍ Plan to increase each beam current by x1.4






Lower σ_y^* from 13 to 9 mm

- ✍ New x-y BPMs at sextupoles in both rings for improved steering
- ✍ New ring correction algorithms (MIA)
- ✍ Better IR coupling control with better lattice model
- ✍ Move horizontal tunes to near half integer
- ✍ Luminosity gain equals 13/9 or ~1.4






The BABAR Detector



- ✂ SVT: 97% efficiency, 15mm z resol. (inner layers, ? tracks)
- ✂ Tracking : ? $(p_T)/p_T = 0.13\%$ $P_T ? 0.45\%$
- ✂ DIRC : K-? separation $>3.4?$ for $P < 3.5 \text{ GeV}/c$
- ✂ EMC: ? $E/E = 1.33\%$ $E^{-1/4} ? 2.1\%$



SVT Summer Shutdown Work



- SVT work performed by a team from Italy and US
- SVT was un-cabled, split in two halves and removed from the B1 magnets




SVT Work

- **Many electrical tests and visual inspections were performed. Identified the cause of the the 9 non functioning readout sections: mainly due to bad connections to the matching cards**
- **During the reassembly procedure we were able to**
 - **Fix six out of nine non functioning sections (non-functioning now: 3 of 208)**
 - **Secure better the connections at the matching cards**
 - **Improve the sealing of the IP and install a humidity control system**
 - **Re-terminate the backward cables**
 - **Install additional radiation sensors (diamond,CsI,quartz)**
- **No new non functioning read-out sections were introduced**



SVT & Support Tube Installation




11/07/2002

HEPAP




DCH Damage and Repair, Summer 2002



- " Support tube hit inner cylinder
- " 6" x 1" crack in beryllium section
- " No environmental contamination
- " IC still about 7x structural load

- " Filled with epoxy
- " Covered with Al



- " Helium tight (< 50 ml/min)
- " Electrically grounded
- " 5 mm clearance to support tube
- " No damage to nearby wires






DIRC shutdown main activity: TDC upgrade (French effort)

Issue: background rate versus luminosity:

→ **expectation: rate (kHz) ~ 530 at $L=4.10^{34} \text{ cm}^2/\text{s}$**



← **high inefficiency with current design**


? **New TDC design to allow small dead time up to 1 MHz rates**

- Binning=520ps, full scale=32? s
- Simultaneous Read and Write operations
- Counting inefficiency < 1% @1MHz
- Minimum time between 2 consecutive L1: 2.2 ? s



DIRC shutdown main activity: TDC upgrade

TDC chips: 12 (sectors) \times 14 (Front End Boards) \times 4 (chips)=672



Sector crate



Front end board

Boards:

- removed and sent to external company for chips exchange
- re-coded and tested in test bench at SLAC
- re-installed in detector

└─ fully tested with calibration data: OK

→ **TDC upgrade successful !**



DIRC shutdown main activity: TDC upgrade (III)


- ✍ TDC fabrication: custom made at LPNHE (Paris)**
 - ✍ Design review: May 4th 2001**
 - ✍ First prototype: mid-October 2001**
 - ✍ Second round of prototype : April 2002**
 - ✍ Full production launched: April 2002**
 - ✍ Chips sent to SLAC: September 18th 2002**
 - ✍ Chips exchanged by company: October 2th 2002**
 - ✍ Boards re-installed and fully tested in detector: October 11th 2002**



IFR Endcap Upgrade


- **Improve pion contamination for tightly identified muons from 2.36% to $< 1\%$**
- **Replace dying RPCs with new chambers that have been carefully QC'd**
- **INFN provides new, improved RPCs**
- **US provides brass absorber, improved HV distribution system, improved gas distribution system**
- **INFN & US: extensive manpower & engineering contributions**

New Forward EndCap project (improve ? -ID)







Forward Endcap: Installation Complete



Installation
Complete

Run=30460, FwdWestMiddle summary



Belt chambers




$\sin(2\beta)$ — Defining our Understanding

$\sin(2\beta)$ constraints
from BABAR

CP violation
in K decays

Semileptonic B
decays (measure
1 side of triangle)

Constraints
from mixing (Δm_d and Δm_s)





Analysis Improvements

Steady improvements

- ✍ Better statistics
- ✍ Better understanding of detector


In 2 years, limit ? discovery ? precision measurement

- ✍ From a test of our understanding ? defining our understanding

Many ever more stringent tests yet to come

- ✍ *CP* violation in more complex decays
- ✍ Rare *B* decays

Rich source of physics at least until the end of the decade — 35 papers in publication





Other Linac Downtime Work

1. Collimators for Möller scattering experiment in End Station A (E158) were improved

- ✍ **Linac commenced running October 1, 2002. E158 will get 5 weeks of running (16 weeks were requested)**
- ✍ **Linac performance has been excellent**

2. Installed bunch compressor in sector 10 which shortens linac pulse by factor of 20



E-158 Collaboration - Institutions

***Caltech
Princeton University
SLAC
CEA Saclay
Smith College***

***Syracuse University
Jefferson Laboratory
UC Berkeley
UMass Amherst
University of Virginia***


- 60 physicists from United States and France
- User groups funded mostly by Medium Energy Physics
- 3 B.S, 1 M.S. and 1 Ph.D. thesis on design
- 7 doctoral students on physics data



SLAC E-158


Left-Right Asymmetry in Fixed Target Moller Scattering

Goal: Most Precise Weak Mixing Angle Measurement at Low Q^2



$$A_{LR} = 0.18 \text{ ppm}$$

$$\delta(A_{LR}) = \pm 7\% \pm 3\%$$




compositeness
 $\Lambda \sim 15 \text{ TeV}$

New Physics

new forces
 $M_{Z'} \sim 1.0 \text{ TeV}$

$$\left| \frac{e_R}{e} \right|^2 - \left| \frac{e_L}{e} \right|^2$$







E-158 Status


- Delivery of total beam power of 550 kW
- Unprecedented stability and accuracy
- Successful operation with PEP-II
- Run I: 5 weeks data run completed, May 03
- Run II in progress, data set will be doubled
- final run in late 2003

Parameter	E158	NLC-500
Charge/Train	6×10^{11}	14.3×10^{11}
Train Length	270ns	260ns
Bunch spacing	0.3ns	1.4ns
Rep Rate	120Hz	120Hz
Beam Energy	45 GeV	250 GeV
e ⁻ Polarization	80%	80%

Preliminary result from 5 week production run



Comparison of E158 and NLC Beam Parameters





E158 Beam Delivery Run2

October 10 – November 15

45 GeV Run 2 Data

October 10 – October 25






E158 Beam Delivery Run2

October 10 – November 15

48 GeV Run 2 Data

October 25 – November 15





E158 Beam Delivery Summary for Runs 1 and 2

	Energy	#days @120Hz	# Peta-Electron	#spills	Average Charge	Production Efficiency*
Run 1	45.6 GeV	19.2	67K	125M	5.5×10^{11}	62%
Run 1	48.8 GeV	14.8	37K	105M	3.5×10^{11}	68%
Run 2	45.6 GeV	15.2	56K	113M	5.2×10^{11}	71%
Run 2	48.8 GeV	20	-	-	4.3×10^{11}	81%**

*Efficiency is avg. delivered rate normalized to 120Hz


**81% efficiency for first 9.5 days @ 48 GeV Run 2

Run 1: April 23 12:00 – May 28 00:00


Run 2: October 10 08:00 – November 15 08:00



Sub-Picosecond Pulse Source




Add 12-meter chicane compressor
in linac at 1/3-point (9 GeV)




80 fsec FWHM

Existing bends compress to <100 fsec



or


Existing bends compress to <100 fsec



10 m undulator
200 periods, K=6



4 Magnet Chicane in Sector 10





SLAC Beam Parameters — Pre and Post SLC

SLAC LINAC FFTB BEAM BEFORE-AFTER SLC+SPPS SPECIFICATIONS

J. Seeman, R. Erickson

14-Oct-02


Parameter	Units	Electrons Before SLC	Electrons After SLC	Electrons After SLC+SPPS	Positrons Before SLC	Positrons After SLC
Energy (E)	GeV	30	47	28	20	47
Particles per bunch (N)	$\times 10^{**8}$	10	400	400	0.33	390
Bunch length (sigz)	mm	3	0.5	0.025	4	0.5
Horizontal invariant emittance	m-rad	3.00E-04	4.00E-05	4.00E-05	2.00E-03	5.00E-05
Vertical invariant emittance	m-rad	3.00E-04	6.00E-06	6.00E-06	2.00E-03	3.00E-06
Absolute horizontal emittance at linac end	m-rad	5.11E-09	4.35E-10	7.30E-10	5.11E-08	5.44E-10
Absolute vertical emittance at linac end	m-rad	5.11E-09	6.52E-11	1.10E-10	5.11E-08	3.26E-11
Average x or y beta function at linac end	m	200	35	35	200	35
Average x beam size at full energy (sigx)	microns	1011	123	160	3197	138
Average y beam size at full energy (sig y)	microns	1011	48	62	3197	34
Energy Density=E*N/sigx/sigy/sigz	GeV/??2/mm	9.78E+03	6.38E+08	4.53E+09	1.61E+01	7.87E+08
Ratio of energy density after-to-before			65184	462692		48721729

In addition: Polarization was increased from 42% to 80%
Fill rate for PEP ring increased from 7 to 720 mamps/min



E-162: Use Imaging Spectrometer To Measure Energy Loss & Gain

**Picosecond
Gaussian
Slice Analysis
of Many Events**




~~✗~~ Average energy loss (slice average): $159 \pm 40 \text{ MeV}$

~~✗~~ Average energy gain (slice average): $156 \pm 40 \text{ MeV}$

($\sim 1.5 \times 10^8 \text{ e-/slice}$)



Do plasma wakes scale as $1/\lambda_z^2$?



**E164 will
Run in FFTB
March-April 2003**



FY03 – A Challenging Budget Year

- ✍ **SLAC budget for FY2003 is \$0.7M less in dollars than our FY 2002 budget**
 - ✍ **Absence of inflation compensation presents the Laboratory with a major challenge**
- ✍ **Dealing with this challenge has required a plan that**
 - ✍ **Makes cutbacks in all the program elements**
 - ✍ **Relies in addition on staff-related cost saving measures**



SLAC Electrical Power Costs

(Dollars in thousands)

	<u>FY1999</u>	<u>FY2000</u>	<u>FY2001</u>	<u>FY2002</u>	<u>Est</u> <u>FY2003</u>
Site Power	610	574	670	865	975
HEP Power	5,023	5,090	5,993	7,872	9,568
Total Power	<u>5,633</u>	<u>5,664</u>	<u>6,663</u>	<u>8,737</u>	<u>10,543</u>



Proposed HEP Program Cuts for FY03

- ✍ **We will do our best to keep the *B* Factory running as close to 38 weeks as the budget will allow. However we are forced to reduce the spending on the *B* Factory machine upgrade by about \$3.5M**
- ✍ **E158 in ESA will only run 5 weeks instead of their requested 16 weeks**
- ✍ **Construction of the photon beamline for the next 3 approved ESA experiments is completely halted. Design of the first experiment is halted. This may portend the cancellation of these experiments**
- ✍ **Funding for the NLC R&D will be below expectations**
- ✍ **All the M&S budgets supported by HEP have been squeezed very hard**
- ✍ **Routine upgrading of desk-top computers will be deferred for a year**
- ✍ **Routine purchases of furniture will be deferred for one year**



Staff-related Measures for FY03

- ✍ Based on our current expectations for the FY03 budget, three staff-related measures are required**
- ✍ Voluntary layoff program**
 - ✍ This program is available to all staff**
- ✍ All HEP-funded staff to take vacation during FY03 equal to at least the vacation earned during FY03**
- ✍ All HEP-funded staff to take leave without pay next September 2,3,4 and 5**
 - ✍ This represents a 1.5% reduction in take-home pay for the year, but does not change the employee's base salary**

SLAC User Lodging Entrance View



SLAC User Lodging Courtyard View





SLAC User Lodging Construction Progress – 11/05/02

