

**07-SC-02 Electron Beam Ion Source
Brookhaven National Laboratory, Upton, New York**

1. Significant Changes

The FY 2008 request represents the balance of construction funding necessary to complete this project. Critical Decision 2, Approve Performance Baseline and Critical Decision 3, Approve Start of Construction, were approved in 4Q FY 2006. This is a joint DOE-NASA project: NASA funding contributions allow for project completion in a more-timely manner, consistent with NASA mission requirements.

2. Design, Construction, and D&D Schedule

(fiscal quarter)

	Preliminary Design start	Final Design Complete	Physical Construction Start	Physical Construction Complete	D&D Offsetting Facilities Start	D&D Offsetting Facilities Complete
FY 2007	1Q FY 2006	4Q FY 2007	2Q FY 2007	2Q FY 2010	N/A	N/A
FY 2008	1Q FY 2006	4Q FY 2007	2Q FY 2007	2Q FY 2010	N/A	N/A

3. Baseline and Validation Status

(dollars in thousands)

	TEC	OPC, except D&D Costs	Offsetting D&D Costs	Total Project Costs	Validated Performance Baseline	Preliminary Estimate
FY 2007	13,700	1,100	N/A	14,800 ^a	4Q FY 2006	14,800 ^a
FY 2008	13,700	1,100	N/A	14,800 ^a	4Q FY 2006	14,800 ^a

4. Project Description, Justification, and Scope

This Project Data Sheet requests construction funding for the Electron Beam Ion Source (EBIS) project at Brookhaven National Laboratory (BNL). Project engineering and design (PED) funding was received in FY 2006 and in FY 2007 under project number 06-SC-02.

The flagship user facility at BNL is the Relativistic Heavy Ion Collider (RHIC), unique in the world for its ability to create a heretofore-unknown state of nuclear matter called quark-gluon plasma. The operation of RHIC supports the scientific mission of the DOE by providing a world-class facility for Nuclear Physics Research. The quark-gluon plasma is created through the collision of heavy ions accelerated to nearly the speed of light. This process is started at the RHIC pre-injector. The present pre-injector for heavy ions for RHIC uses the Tandem Van de Graaff, built around 1970. The beam is transported to the Booster via an 860 m long line.

The EBIS project will provide a new heavy ion pre-injector for RHIC based on a high charge state heavy ion source, a Radio Frequency Quadrupole (RFQ) accelerator, and a short Linear Accelerator (Linac). The highly successful development of an Electron Beam Ion Source at BNL now makes it possible to replace the present pre-injector that is based on electrostatic Tandems with a reliable, low maintenance Linac-based pre-injector.

Linac-based pre-injectors are presently used at most accelerator and collider facilities with the exception of RHIC, where the required gold beam intensities could only be met with a Tandem until the recent EBIS development. EBIS produces high charge state ions directly, eliminating the need for two

^a The costs presented in this Project Data Sheet include the costs for PED from project 06-SC-02. NASA has contributed an additional \$4,500,000 to the DOE TPC.

stripping foils required with the Tandem. Unstable stripping efficiency of these foils is a significant source of luminosity degradation in RHIC. The high reliability and flexibility of the new Linac-based pre-injector will lead to increased integrated luminosity at RHIC and is an essential component for the long-term success of the RHIC facility. This new pre-injector based on an EBIS also has the potential for significant future intensity increases and can produce heavy ion beams of all species including uranium beams and could also be used to produce polarized ^3He (Helium) beams. These capabilities will be critical to the future luminosity upgrades and electron-ion collisions in RHIC.

The new RFQ and Linac are used to accelerate beams from EBIS to an energy sufficient for Booster injection. Injection into the Booster will be at the same location as is used for beams from the Tandem.

The new pre-injector will be installed in the lower equipment bay of the existing 200 MeV Linac Building. Modifications to this building will be required to provide an injection path into the Booster and house the new equipment.

In summary, the proposed new pre-injector offers the following advantages:

- The EBIS replaces the 35 year-old Tandems with a modern, Linac-based pre-injector.
- The RFQ and linac technology is simpler, more modern and robust, and will require significantly less effort to maintain.
- The 860 meter long Tandem-to-Booster transport line will be replaced with a 30 to 40 meter transport system.
- The EBIS eliminates current limitations on ion species. Because injection from the Tandems must start with negative ions, not all species can be accelerated. The EBIS can produce any ion species.
- The single EBIS would allow pulse-to-pulse switching between any two species. This increased flexibility will provide the ability to meet the multiple, simultaneous needs of RHIC, NASA, and the Alternating Gradient Synchrotron (AGS). Presently, two tandems are needed for fast beam switching, while the new pre-injector will be able to switch species on a pulse-to-pulse basis.
- Beam stability will be improved with the elimination of stripping foils now required in the tandems.
- The addition of the EBIS pre-injector has the potential to reduce operations costs. The Tandem facility requires a staff of about 12 FTE's to support maintenance and a 24-hour shift rotation during operations. The Linac-based pre-injector will run unattended at most times, as with the present proton linac, and will require a staff of about 3 FTE's to maintain.

The replacement of the existing ion source at Brookhaven National Laboratory (BNL) with the proposed EBIS offers additional capabilities to NASA in the operation of the NASA Space Radiation Laboratory (NSRL) at BNL. NASA is providing a total of \$4,500,000 in funding, reducing the Total Project Cost of EBIS to DOE, in order to accelerate the project profile and decrease project duration.

Compliance with Project Management Order

The project will be conducted in accordance with the project management requirements in DOE Order 413.3A and DOE Manual 413.3-1, Program and Project Management for the Acquisition of Capital Assets. The project costs presented in this Project Data Sheet are baselined costs for project engineering design and construction.

The EBIS project received CD-0 approval in the 4Q FY 2004 and CD-1 approval in the 4Q FY 2005. A DOE review of technical scope, cost, schedule, and management was held in May 2006 and the project was found to be progressing well. The Performance Baseline and Approval for Start of Construction were validated in the 4Q FY 2006 after an Independent Project Review.

- Critical Decision – 0: Approve Mission Need – 4Q FY 2004
- Critical Decision – 1: Approve Alternative Selection and Cost Range – 4Q FY 2005
- Critical Decision – 2: Approve Performance Baseline – 4Q FY 2006
- Independent Project Review Final Report – Date: 4Q FY 2006
- Critical Decision – 3: Approve Start of Construction – 4Q FY 2006
- Critical Decision – 4: Approve Start of Operations – 2Q FY 2010

5. Financial Schedule

(dollars in thousands)

Appropriations	Obligations	Costs
----------------	-------------	-------

Design/Construction by Fiscal Year

Design

2006	1,980	1,980	1,322
2007	120	120	778
Total, Design PED (06-SC-02)	2,100	2,100	2,100

Construction

2007	7,400	7,400	4,400
2008	4,200	4,200	5,200
2009	—	—	2,000
Total, Construction	11,600	11,600	11,600

Total DOE TEC	13,700	13,700	13,700
---------------	--------	--------	--------

6. Details of Project Cost Estimate

Total Estimated Costs

	(dollars in thousands)	
	Current Estimate	Previous Estimate
Preliminary and Final Design (PED No. 06-SC-02)	2,100	2,100
Construction Phase		
Site Preparation	695	695
Equipment	8,360	8,360
Contingency	2,545	2,545
Total, Construction	11,600	11,600
Total, DOE TEC	13,700	13,700

Other Project Costs

	(dollars in thousands)	
	Current Estimate	Previous Estimate
Conceptual Planning	200	200
R&D	600	500
Start-up	250	250
Contingency for OPC other than D&D	50	150
Total, DOE OPC	1,100	1,100

7. Schedule of Project Costs

	(dollars in thousands)							Total
	Prior Years	FY 2008	FY 2009	FY 2010	FY 2011	FY 2012	Outyears	
TEC(Design)	2,100	—	—	—	—	—	—	2,100
TEC (Construction)	4,400	5,200	2,000	—	—	—	—	11,600
OPC Other than D&D	800	100	200	—	—	—	—	1,100
Total, Project Costs	7,300	5,300	2,200	—	—	—	—	14,800

8. Related Operations and Maintenance Funding Requirements

Start of Operation or Beneficial Occupancy (fiscal quarter)	2Q FY 2010
Expected Useful Life (number of years)	25
Expected Future start of D&D for new construction (fiscal quarter)	1Q FY 2035

(Related Funding Requirements)

Costs to operate EBIS are included in the RHIC Operations budget and they are not considered incremental costs.

9. Required D&D Information

This upgrade project will not create any new building square footage, and thus is not subject to the “one-for-one” replacement requirement.

10. Acquisition Approach

The Acquisition Strategy was approved in 4Q FY 2005 with CD-1 approval. Design and inspection of the facilities and equipment will be by the operating contractor and Architect-Engineer (A-E) subcontractor as appropriate. A-E design services will be done by a combination of BNL and competitively bid lump sum contracts administered by the BNL. To the extent feasible, procurements will be accomplished by fixed-price contracts awarded on the basis of competitive bidding. Project and design management, inspection, coordination, tie-ins, testing and checkout witnessing, and acceptance will be performed by the BNL operating contractor.